

Shasta County Office of Education

Addendum No. 1

Date: 2024/06/13

Project: AV Installation Project at 1177 Placer Street

To: Prospective Bidders

The following changes, modifications and additions to the Contract Documents described below are made a part thereof and are subject to all of the requirements thereof as if originally specified. The submitter must acknowledge receipt of the Addendum in the space provided below and submit a copy of each addendum with their respective bid. Failure to do so may subject the bidder to disqualification.

Item # 1 – Important Dates

Notice to Bidders Issued: June 2, 2024

RFI Deadline: June 17, 2024*

Sealed Bids Due: ~~June 18, 2024~~ **June 27, 2024**

Selection by SCOE: ~~June 24, 2024~~ **July 3, 2024**

Item #2 – The Notice to Bidders shall be amended as follows:

“The deadline for Completion is August 7, 2024. See Article III of the Agreement for details.

All Requests for Information (“RFI”) shall be submitted to Owner’s representative no later than 5:00pm on June 17, 2024.

Bids must be sealed and filed at Owner’s administrative office in the following building:

1644 Magnolia Avenue
Redding, California 96001

on June 27, 2024, before 3:00 p.m. on the clock designated by the Owner or its representative as the bid clock. No bid will be accepted by the Owner after this time. Facsimile (FAX) copies of the bid will not be accepted. Bids may be opened immediately after the above deadline for submittal, or at a later time, within the Owner’s discretion.”

Item #3 - Response to Bidder’s Questions.

1.1 Question: When can existing systems be viewed?

Answer: A walk through of our existing switching systems can be scheduled by calling (530) 225-0279, requesting a tour of an existing system and referencing this bid.

1.2 Question: What specifics are requested for the displays:

Answer:

Room 1 - 100" display for side and front of room (need to cover areas which are approximately 7'x4' each), 22" monitor next to the switching equipment

Room 2 - 75" interactive touch screen with built in PC

Room 3 - 85" interactive touch screen with built in PC

Room 4 - East side of room (front), 120" Display (needs to cover an area approximately 8'x6'), South side of room (side) 100" Display (needs to cover an area approximately 7'x4'), West side of room (Rear - up high) 100" Display for the west side of the room (above the desk area) (needs to cover an area approximately 7'x4') Swivel mount to allow it to cross the corner offers both a direct wireless display as well as switched display from this rooms switching equipment, 22" monitor next to the switching equipment

Room 5 - 85" interactive touchscreen display w/built in PC

1.3 Question: Other specifics for each room to be clarified

Answer:

Room 1 - PTZ Camera placed in the North-west corner of the room with a wide enough angle to cover the room as well as the ability to swivel to cover speakers in other locations of the room. Full room coverage mics + 1 wireless handheld mic, Room speakers, floor standing rack cabinet for equipment (see photo for an example) with a minimum of 3ru free space for an owner provided PC, Crestron touch display stands on top of the rack cabinet (see photo for an example), lectern with monitor (see example photo), Switcher output to the wall for the lectern to plug into. All displays controllable from the crestron matrix switcher.

Room 2 - Camera to comfortably cover the participants in the room, Speakers to cover the room but not necessarily ceiling mounted, Mounted Mic to cover the room (not necessarily ceiling mounted). No handheld mic, No need for Crestron switching or control panel

Room 3 - Camera to comfortably cover the participants in the room, Speakers to cover the room but not necessarily ceiling mounted, Mounted Mic to cover the room (not necessarily ceiling mounted). No handheld mic, No need for Crestron switching or control panel, Wired HDMI from an input on the display to the center of the conference table.

Room 4 - 19" wide rack for AV equipment with a minimum of 3ru free space for an owner provided PC, PTZ Camera mounted on the west side of the room facing the front screen. speakers to cover the primary meeting area as well as the overflow, mounted room mic(s) to cover primary meeting area, wireless handheld and lapel mics, lectern with monitor (see

example photo). Switcher output to the wall for the lectern to plug into. All displays controllable from the rooms Crestron matrix switcher.

Room 5 - Camera to comfortably cover the participants in the room, Speakers to cover the room but not necessarily ceiling mounted, Mounted Mic to cover the room (not necessarily ceiling mounted). No handheld mic, No need for Crestron switching or control panel.

Example 1 - floor standing rack cabinet for equipment. See also the Crestron control panel on top of the cabinet and 22" monitor mounted to allow easy set up of the displays.



Example 2 - Lectern with monitor



I HAVE READ AND UNDERSTOOD ALL PAGES OF ADDENDUM NO. 1 OF THE ABOVE
BID:

Signature: _____